

# Offshore Wind Risks - Issues and Mitigations

**DNV Offshore Wind**

Soren Karkov  
October 2010

# DNV – an independent foundation



## Our Purpose


**To safeguard life, property  
and the environment**

## Our Vision

**Global impact for a safe  
and sustainable future**

# More than 145 Years of Managing Risk

- DNV (Det Norske Veritas) was established in 1864 in Norway
- DNV is a leading international provider of services for managing risk
- DNV is a foundation and reinvests all profits in services, research and development




# DNV – An Independent Foundation



# A trusted player in shipping



# Expert role in the oil and gas industry



65%

65% of the world's offshore pipelines are designed and installed to DNV's pipeline standard

40%

40% of the world's Floating Production, Storage and Offloading vessels (FPSOs) are to DNV class

30%

30% of the world LNG terminal projects are supported by DNV

# Impacting climate change issues



1st

Released the world's first standard for qualification of carbon capture technology

48%

48% of all Clean Development Mechanism (CDM) projects are validated by DNV

75%

75% of the world's offshore wind projects are certified and verified by DNV

Global

Developed a global rating scheme for monitoring ships' environmental performance



# Services to the Wind Industry

## Advisory Services


- Wind Resource Assessment
- Project Development Support
- Due Diligence
- Marine Advisory Services
- Asset Risk Management
- Wind Turbine Technology
- Health, Safety and Environmental Risk Management
- Training and Educational Programs

## Accredited Services


- Project Certification
- Type Certification
- Testing Services
  - Power Performance Testing
  - Loads Testing




# Major Risks in Offshore Wind Farms



# Onshore – Offshore Wind Farms Project Costs



# Onshore – Offshore Wind Farms Project Costs



■ Project Development ■ Financing and Legal ■ Construction ■ Balance of Plant ■ Turbine Costs

# Wind Energy Uncertainty

## ■ Issue

- Reliability of kWh generated estimates
- Real on-site data are scarce
- Wind resource estimates have large uncertainty
- Loss factors are not well understood (e.g. wakes and turbulence)
- Potential large variation in wind resource across the site

## ■ Mitigation

- Offshore measurement (fixed tower, novel solutions) over sufficient period of time (> 2 years)
- Layout optimisation and understanding the trade-offs
- Transparency of energy estimates

100 MW – 5% off – 20 years – 22 MUSD




# Site Conditions – Marine Environment

## ■ Issue

- The weather and sea conditions
- Varying water depths and sea bed conditions across a site
- Weather window for offshore work is small

## ■ Mitigation

- **Solid, site-specific information**
  - Measurement campaigns
  - Data mining
  - Geotechnical investigation
  - Safety factors in design
- **Relevant learning from oil and gas**
- **Development / use of equipment / methods suitable in adverse conditions**



# Wind Turbine Technology

## ■ Issue

- Large MW turbines required 10 MW?
- Component failures difficult to rectify offshore

## ■ Mitigation

- Turbine selection
- Strong warranty agreements
- Condition monitoring
- Data monitoring, analysis and response
- Proactive maintenance
- Further research into design loadings
- Turbine type certification




# Wind Turbine Foundations

## ■ Issue

- **Costly foundation designs due to:**
  - Harsher marine conditions
  - Deeper water
  - Larger turbines
- **Shallow-water solutions may not work**

## ■ Mitigation

- **Standardisation**
- **Quality control during manufacture**
- **Information sharing between WTG manufacturer and foundation designers for benefit**



# Subsea Cables and Power Transmission

## ■ Issue

- Many problems during cable installation, e.g. improper cable handling
- Human introduced hazards (e.g. anchoring)
- Natural hazards (seabed mobility)
- Unplanned downtime not considered in energy estimates


## ■ Mitigation

### - Cabling

- Understand site-specific conditions
- Chose appropriate cabling design (e.g. armour, burial depth, scour protection)
- Work with experienced partners
- Plan with contingencies

### - Substation

- Realistic expectations for annual maintenance time
- Include unplanned outages
- Diligent inspections and maintenance



# Construction

## ■ Issue

- Major project
- Contract strategy selection
- Managing the interfaces
- Supply chain and facilities
- Unexpected technical issues

## ■ Mitigation

- Previous project experience
- Project lifecycle engineering supervision
- Installation concept studies
- Develop your own team
- Plan A, B and C
- Project Certification



# Offshore Access

## ■ Issue

- Current access solution (boat fendering) limited by sea state (e.g. < 1.5 m significant wave height)
- Access to turbines more frequent than expected
- Health and safety issues – reputational risk

## ■ Mitigation

- Improvement of current solutions (e.g. to 3 m significant wave height)
- New access solutions (e.g. heave-compensated gangway)
- Additional access by helicopter-hoisting



# Grid Connection

## ■ Issue

- Load centers far away from offshore wind farm
- Congestion in certain areas of the grid
- Long distance / high power will require (less proven) offshore HVDC solutions
- Uncertainty about ownership / operation of assets

## ■ Mitigation

- Early dialogue between developer and grid operator
- Careful evaluation of various options




Diagram to demonstrate the proposed regime for offshore transmission


# Construction Vessels

## ■ Issue

- Vessels are scarce and expensive (e.g. +200 k\$/day + mob/demob)
- Capabilities (crane, deck space, propulsion) limited
- Vessel reliability

## ■ Mitigation


- Developers building own vessels
- Long-term contracts (but uncertainties about project schedules)



# Offshore Wind: Need for new installations vessels

- China have a target for 2020 of 30 GW offshore wind power capacity
- 40 GW of offshore wind capacity in the EU by 2020
- Assumption: Turbine size = 3 MW and 1 vessel installs 100 turbines per year

No of Installation Vessels



Conclusion:

20-25 vessels needed in Asia

30-35 vessels needed in Europe

+ vessels for foundation and maintenance & repair

- Lead time: 3 – 5 years

# Project Certification




# Project Certification

---

- **Third party conformity evaluation of**
  - One or more wind turbines at a **specific location**
  - From design evaluation to monitoring of commissioning and operation
  
- **Project Certificate covers**
  - One or more **wind turbines, including the foundation's**
  - Evaluated for the **specific external conditions at an installation site**
  - **No period of validity**

# Project Certification – DNV-OS-J101




Project Certification phases:

- Phase I : **Verification of Design Basis**
- Phase II : **Verification of Design**
- Phase III : **Manufacturing Survey**
- Phase IV : **Installation Survey**
- Phase V : **Commissioning Survey**
- Phase VI : **In-Service**

Each phase will be completed with a **Statement of Compliance**



- Phase I-V => *Project Certificate*
- Phase VI => *Certificate Validation*

# Type Certification & Project Certification




# Verification of Design Basis

- **Site Conditions**
  - meteorological conditions
  - oceanographic conditions
  - geotechnical conditions
- **Codes, Standards and Requirements**
- **Design Methodology**
- **Wind Turbine Type Certificate**
- **Grid Connection**
- **Installation and Commissioning**
- **Operation and Maintenance**




# Verification of Design

- **Verification of Load and Response for the integrated structure**
  - Rotor-nacelle
  - Sub-structure
  - foundation
- **Verification of Wind Turbine**
- **Verification of Support Structure**
- **Verification of Substation, Cables and J-tubes**
- **Verification of Installation and Commissioning Procedures**
- **Verification of Operation and Maintenance**




# Manufacturing Survey

- Manufacturing Survey of Wind Turbine
- Manufacturing Survey of Support Structure and Substation structure
- Manufacturing Survey of Electrical Components and Systems




# Installation Survey


- **Marine Verification**
  - Installation procedure
  - Installation survey
- **Warranty Survey**



# Commissioning Survey


- Review/approval of procedures
- System check
- Equipment Checks

 <b>DET NORSKE VERITAS</b>	
<b>PROJECT CERTIFICATE</b>	
Number 643XXX-PCXX-REVXX	
Name/Designation/Description of the Object: <b>XXXX OFFSHORE WIND FARM</b>	
Owner(s): <b>XXXX</b>	
THIS IS TO VERIFY that the above mentioned object has been appraised and/or surveyed during the <b>Design, Fabrication, Installation, hook-up and Commissioning Phase(s)</b> According to Contract no. XXXX and after DNV's best knowledge and understanding found to comply with: <b>List of relevant standards, rules and national requirements</b>	
Reference documents (reports etc.): <b>Reappraisal report 643XXX-XXXX-XXXX</b>	
Validity: This certificate remains valid until 20XX-XX-XX provided the terms in In-service Contract XXXX are complied with.	
Issued at <b>Det Norske Veritas Danmark A/S</b>	Date <b>200X-XX-XX</b>
<i>for Det Norske Veritas</i>  Jan Behrendt Ibsø General Manager	
<b>DET NORSKE VERITAS, DANMARK A/S</b>	



# In-service

- **Annual Survey Onshore Part**
  - Review of Maintenance, Repair Program
  - Inspection Program
- **Annual Survey Offshore Part**
  - All main components in Wind Turbines
  - Structures and Cables below water
  - Substation Topside all main components/systems



# Safeguarding life, property and the environment

[www.dnv.com](http://www.dnv.com)



MANAGING RISK